

NATIONAL INSTITUTE OF DESIGN  
EEE BLOCK, ANU CAMPUS , GUNTUR  
ANDHRA PRADESH

No.F NID-AP/LBM/Stores/1203/2019

**NOTICE INVITING QUOTATION**

1. Percentage rate quotations are invited for the work of “Repair /Renovation of Existing floors of Transit Campus of NID AP” from experienced agencies.
2. Estimated cost of the work is Rupees Rs. 4, 94, 269/-- (Four Lacs Ninety Four Thousand Two Hundred Sixty Nine Only). The time allowed for completion of work is 30 days from the date of issue of letter of award.
3. NIQ documents may be downloaded from the website [www.nid.ac.in](http://www.nid.ac.in) from 07.02.2019 to 12.02.2020 and the downloaded documents shall be submitted to the office of the Senior Engineer (Land, Building and Maintenance ), National Institute of Design, Andhra Pradesh , EEE &ECE Building , Ground floor , Acharya Nagarjuna University, Nagarjuna Nagar , Guntur (A.P.)-522510 on all working day up to 12.02.2020 , 11:00 AM and will be opened at 11:30 A.M. on the same day.
4. The submitted documents shall only be opened subject to fulfilment of following conditions:-

4(i) Agencies shall submit the NIQ document in two sealed envelopes in the following manner:-

**Envelope -1**

- 1) Copy of PAN Card
- 2) Registration certificate under Good and Service TAX( GSTIN)

**Envelope -2 (Financial bid of technically qualified bidders shall only be opened)**

- 1) Duly signed NIQ document downloaded from the web & Price Bid

**Envelope – 3**

Both envelopes should be enclosed in a common Envelope-III. In case Envelope-I is not annexed then Envelope-II containing NIQ document & Price Bid will not be opened at all.

**5 EARNEST MONEY- Nil**

**6 TERMS & CONDITIONS**

1. Schedule of Quantity as per Annexure A
2. Time allowed –30 Days
3. Any damage done to the equipment /building during execution of work shall be on part of Supplier
4. Recovery will be made as per rules
5. The quoted rates are inclusive of Good and Services Tax , labour cess etc and nothing extra shall be payable on this account

(Abhishek Agrawal)  
Senior Engineer (Land, Building and Maintenance)

**SCHEDULE OF QUANTITY**

<b><u>Name of work - Repair/Renovation of existing floors of Transit Campus of NID Building</u></b>						
Sl no.	DSR -18 Item no.	Description	Unit	Qty	Rate	Amount
1	15.25	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	sqm	150	190.3	28545
2	4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	cum	18	5789.6	104213
3	11.26.1	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand 25 mm thick)	sqm	230	1531.85	352325.5
4	1.1.18	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge	cum	15.08	284.6	4292
		Total Cost				<b>489375</b>
		<b>Percentage to be quoted (Below /Above ) (+/-)</b>				

\_\_\_\_\_  
**Agency**  
**Seal & Addresses**

\_\_\_\_\_  
**Senior Engineer (LBM)**